

One Water and Stewardship Committee Annual Climate Action Plan and Update on Climate Vulnerability and Risk Assessment

Item 7c May 8, 2023

Increasing Climate Resilience



Resilience

Metropolitan builds climate resilience by continuing to reduce its GHG emissions & by investing to manage more frequent & severe climate hazards.

Climate Adaptation Master Planning Process



CAP Progress Update

Climate Mitigation

Key Actions & Successes

- SRI Office and SRI Council formed to ensure CAP success
- Formed the Zero Emission Vehicle Executive Task Force
- Saved 93,500 MT CO₂e in 2021 by implementing green energy procurement measures due to Measure E-5
- Significantly outperforming the turf replacement and water savings targets set in Measure WC-3
- Ahead of schedule in retrofitting lighting to LED technologies
- Renewable diesel pilot project completed in 2021 at Lake Mathews fuel depot
- Three Battery Energy Storage System (BESS) projects have been planned with completion date targets of late 2023 (Weymouth WTP) and early 2025 (Skinner and Jensen WTPs)

Summary of Implementation Progress

Quantifiable Measures

			Year
	AF-3: Renewable diesel	26%	2025
	DC-2: 50% reduction natural gas usage	17%	2030
	E-2: Utilize hydropower at Diemer	0%	2030
	E-3: 100% green retail electricity	47%	2025
	E-4: 3.5 MW Battery Energy Storage	0%	2030
50	E-5: CAISO wholesale electricity	45%	2030
	EE-1: Convert 50% lighting to LED	92%	2030
	EC-3: 15% of employee vehicles are ZEVs	No Data	2025
	EC-5: 50% of HQ employees work from home	No Data	2030
200	WA-1: 30% reduction in landfilled waste	No Data	2030
	WC-3: Remove an average of 1.5 million sq. ft. of turf annually thru 2030	88%	2030
		90% 100	0/

Supportive Measures

Target



No Action or Pending
Underway
Complete or Ongoing

Item # 7c Slide 5



Saved **93,500 MT CO_2e** in 2021 by implementing energy procurement measures due to Measure E-5.

This is equivalent to taking **20,807 gasoline-powered cars** off the road for one year.

Measure E-5

Switching to CAISO from AZNM electricity for CRA pumping led to emissions savings

Measure WC-3

Achieved 88% of the 2030 turf removal target



The estimated water savings from turf replacement projects in Metropolitan's service area from 2017 through 2022 is approximately **9,393 acre-feet**, which translates to saving an average of 855 MT CO_2e per year.

This is equivalent to saving over **4,600 Olympic-sized swimming pools** of water since 2017 and taking 190 cars off the road per year.

Climate Vulnerability & Risk Assessment

Climate Adaptation



Climate Vulnerability & Risk Assessment



May 8, 2023

One Water and Stewardship Committee

Item # 7c Slide 9

Severe Storms

Precipitation from larger and less frequent events (Climate Whiplash)





Identified Climate Hazards



- Drought and Wildfire were the most assessed climate hazards
- Energy-related documents thoroughly identified climate hazards

May 8, 2023

Literature Review

64 Total Documents: 11 Internal and 53 External



Initial Findings

Documentation **decreases** across the spectrum of characterizing hazards, assessing impacts, & developing adaptation actions

Castaic Lake Turbidity Event

Metropolitan is already managing climate extremes





Delta Island Projects

Metropolitan is securing grant funds to support new adaptation investments



Metropolitan is exploring adaptation options along the CRA



Next Steps

Integrate work into the Climate Adaptation Master Planning Process

Climate Mitigation

- Continue implementation of GHG reduction measures
- Develop ZEV Fleet Transition Roadmap
- Renewable energy and storage investments
- Pursue carbon sequestration opportunities
- Initiate quantification of Scope 3 emissions

Climate Adaptation

- Complete Climate Vulnerability Risk Assessment
- Develop Economic Consequence Matrix to connect assessments of hazards & impacts to CAMP4W, adaptation projects, CIPs, and budget

